

To: 1 060095
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-16
API NUMBER 15- 135-23,601-00-0102
100' N of
C NW, SEC. 27, T 16 S, R 21 W
4060 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6569

Lease Name Hinman Well # 1

Operator: Carmen Schmitt, Inc.

County Ness 138.12

Name & Address P.O. Box 47

Well Total Depth 4250 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 416

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Company, Inc. License Number 5929

Address 310 W. Central, Suite 117, Wichita, KS 67202

Company to plug at: Hour: 10 p.m. Day: 15 Month: 9 Year: 19 91

Plugging proposal received from Jay Snider

(company name) Duke Drilling Company, Inc. (phone) 316-267-1331

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1573-1608'

1st plug at 1630' with 50 sx cement, 2nd plug at 1050' with 80 sx cement,

3rd plug at 450' with 60 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:45 a.m. Day: 16 Month: 9 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 1630' with 50 sx cement,

2nd plug at 1050' with 80 sx cement,

3rd plug at 450' with 60 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 18 1991
09-18-1991
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (operator) did not observe this plugging.

DATE 10-16-91

Signed _____ (TECHNICIAN)

INV. NO. 33364

FOR KCC USE:

793-3354

FORM C-1 7/91

EFFECTIVE DATE: 9-9-91

FORM MUST BE TYPED

DISTRICT #

FORM MUST BE SIGNED

SEAT... Yes No

NOTICE OF INTENTION TO DRILL 15-23, 601-00-00

ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date September 6, 1991

Spot 100' N. of C-NW Sec 27 Twp 16 S. Rg 21 East West

OPERATOR: License # 6569
Name: CARMEN SCHMITT, INC.
Address: P.O. Box 47
City/State/Zip: Great Bend, Kansas 67530
Contact Person: Carmen Schmitt
Phone: 316/793-5100

4060 feet from South North line of Section
3960 feet from East West line of Section
SECTION X REGULAR IRREGULAR

CONTRACTOR: License # 5929
Name: DUKE DRILLING CO. INC.

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Ness

Well Drilled For: Well Class: Type Equipment:
X Oil Enh Rec X Infield X Mud Rotary
Gas Storage Pool Ext Air Rotary
OAWD Disposal Wildcat Cable
Seismic: # of Holes Other

Lease Name: Hinman Well # 1
Field Name: Bellespirt

If OAWD: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth:

Is this a Prorated/Spaced Field? yes X no
Target Formation(s): Miss

Directional, Deviated or Horizontal Well? yes X no
If yes, true vertical depth:
Bottom Hole Location:

Nearest lease or unit boundary: 1220'
Ground Surface Elevation: 2277' foot NSL

Exp. 3/4/92
The undersigned hereby affirms that completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Water well within one-quarter mile: yes X no
Public water supply well within one mile: X yes no

Depth to bottom of fresh water: 100'
Depth to bottom of usable water: 925'

Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 200'

Length of Conductor pipe required: N/A
Projected Total Depth: 4400'

Formation at Total Depth: Mississippian
Water Source for Drilling Operations:

well farm pond X other
DWR Permit #:

Will Cores Be Taken? yes X no
If yes, proposed zone: 200' Alt. IT Reg.

RECEIVED STATE COMMISSION SEP 18 1991 AFFIDAVIT *Prorated for Cherokee*

Pusher JAY
SPUD DATE 9-7-1991 INIT. GB
LENGTH SURFACE PLANNED 200' 8 1/2"

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2" @ 4/6 CONDUCTOR
ANHYDRITE T- 2 1/2" B- 1608 ELEVATION

TD 4250 FORMATION MISSISSIPPIAN
RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N

Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX

Anhydrite Base @ 1630 Ft. W/ 50 SX
1/2 Base Anyh. @ 1050 Ft. W/ 80 SX

1/2, 1/2 Plug @ 450 Ft. W/ 60 SX
Bottom Surface @ Ft. W/ SX

40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 5 SX MOUSE HOLE W/ SX

WATER WELL SX (Irr. Well Pond
TECHNICIAN CM DATE 9-12-91 Hauling

TYPE OF CEMENT 60/40 6% 1/4 # floor
STARTING TIME 10:00 (AM/PM) DATE 6-15-91

COMPLETION TIME 1:45 (AM/PM) DATE 6-15-91
CEMENT COMPANY ALLCO