

1 030501

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-22,909-00-00

SE SE SW, SEC. 27, T 16 S, R 21 W E

330 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6249

Lease Name Stevens Well # 3

Operator: Zenith Petroleum Corp.

County Ness 137.96

Name & Address 1235 North Loop W., Suite 919

Well Total Depth 4245 Mississippi feet

Houston, TX 77008

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 760

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A x

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Revin Drilling, Inc. License Number 5671

Address P. O. Box 293, Russell, KS 67665

Company to plug at: Hour: 8:00 am Day: 30 Month: August Year: 1985

Plugging proposal received from Paula

(company name) Revin (phone) 913-483-5355

Elevation 2230 GL

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1519'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 30' out of the surface pipe with 40 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None x

Operations Completed: Hour: 10:15 am Day: 30 Month: August Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 1554' with 50 sx cement, 2nd plug at 800' with 40 sx  
cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with  
10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 6 1985  
09-06-1985

Remarks: Used 60/40 Pozmix 6% gel by Halliburton  
(if additional description is necessary, use BACK WICHITA, KANSAS Form.)

R.M.L.

INVOICED

DATE SEP 10 1985

Signed Steve Durrant  
(TECHNICIAN)

INV. NO. 9920