

1 070375

7-22-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,141 -00-00

NW SE SW, SEC. 24, T 16 S, R 21 W/E
990 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5399

Lease Name Baus "B" Well # 1

Operator: American Energies Corporation
Name &
Address 155 North Market, Suite 710
Wichita, KS 67202

County Ness 136.40

Well Total Depth 4197 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 302

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Beredco, Inc. License Number 5147

Address 401 East Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 5:35 p.m. Day: 22 Month: 7 Year: 19 87

Plugging proposal received from Howard Cain

(company name) Beredco, Inc. (phone) 316-653-2463

were: to fill hole with heavy mud and spot cement through drill pipe
Elevation 2210' GL
Anhydrite 1487-1523'

1st plug at 1500' with 50 sx cement, 2nd plug at 750' with 75 sx cement,

3rd plug at 330' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 7:30 p.m. Day: 22 Month: 7 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1500' with 50 sx cement,

2nd plug at 750' with 75 sx cement,

3rd plug at 330' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.

(If additional description is necessary, use BACK of this form.)

I (did / ~~not~~) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION
JUL 29 1987
07-29-1987
CONSERVATION DIVISION
Wichita, Kansas

Signed Dan Goodrow
(TECHNICIAN)

DATE 7-29-87

INV. NO. 17636
7-22 SEP 1 1987

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date July 16 1987
month day year

API Number 15-135-23, 41, 24-11

OPERATOR: License # 5399
Name American Energies Corporation
Address 155 N. Market, Suite 710
City/State/Zip Wichita, KS 67202
Contact Person Alan L. DeGood
Phone 263-5785

NW SE SW Sec 24 T16 R21
990 Ft. from South Line of Section
3630 Ft. from East Line of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5147
Name BEREDCO, INC.
City/State Wichita, KS

Nearest lease or unit boundary line 990 feet
County NEBA
Lease Name BAYB
Ground surface elevation feet MSL
Domestic well within 500 feet yes X no
Municipal well within one mile yes X no
Depth to bottom of fresh water 200
Depth to bottom of usable water 650
Surface pipe by Alternate 1 2 X
Surface pipe planned to be set 300
Conductor pipe required
Projected Total Depth 4200 feet
Formation MIAOIAIDIAI

Well Drilled For Well Class Type Equipment
X Oil SWD Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl X Wildcat Cable

If OWWO: old well info as follows
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date Signature of Operator or Agent Alan L. DeGood Title VICE-PRESIDENT

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. X
This Authorization Expires 1-15-88 Approved By 7-15-87

Move IN 7-17-87 set 300 894

NW SE SW Sec 24 T16 R21

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays)

1st plug @ 1500	feet depth with 30	szs of Poz Mix
2nd plug @ 650	feet depth with 75	szs of Poz Mix
3rd plug @ 300	feet depth with 50	szs of Poz Mix
4th plug @ 140	feet depth with 10	szs of Poz Mix
5th plug @ 15	feet depth with	szs of
(2) Rathole with 15	szs	(b) Mousehole with 10 szs

PUSHER <u>Howard Caine</u>	FORMATION
TD	
SURFACE PIPE <u>8 5/8 @ 302</u>	
ANHYDRITE <u>1523</u> ELEVATION	
STARTING TIME & DATE <u>5 PM 7-22-87</u>	
COMPLETION TIME & DATE	
1st PLUG @ <u>1500</u> FT. W/ <u>50</u> SX	
2nd PLUG @ <u>750</u> FT. W/ <u>75</u> SX	
3rd PLUG @ <u>330</u> FT. W/ <u>40</u> SX	
4th PLUG @ <u>40</u> FT. W/ <u>10</u> SX	
RAT HOLE CIRCULATED W/ <u>15</u> SX	
MOUSE HOLE CIRCULATED W/ <u>10</u> SX	
WATER WELL PLUGGED W/	
CEMENT COMPANY	
TECHNICIAN	

RECEIVED
STATE CORPORATION COMMISSION
JUL 29 1987
Wichita, Kansas
07-29-1987

60/40 6/9/87
In on how