

1 090253

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22,714-00-00

W/2 NE SW, SEC. 24, T 16 S, R 21 W/E

1980 feet from ~~X~~YS section line

3630 feet from ~~X~~ZE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8572

Lease Name Baus Well # 1

Operator: The Reach Group

County Ness 135.36

Name & Address 3751 East Douglas

Well Total Depth 4165 feet

Wichita, KS 67218

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Robert-Gay Energy Enterprise, Inc. License Number 8059

Address 1006 North Main, Hutchinson, KS 67501

Company to plug at: Hour: 8:00 pm Day: 24 Month: November Year: 19 84

Plugging proposal received from Bud Benoit

(company name) Robert Gay (phone) 316-669-8164

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1500' with 50 sx cement

2nd plug at 750' with 50 sx cement

3rd plug at 360' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by R. Barlittan
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:45 pm Day: 24 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1500' with 50 sx cement, 2nd plug at 750' with 50 sx

cement, 3rd plug at 360' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15

sx cement.

STATE OF KANSAS
11-28-1984
NOV 28 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun.

COMMISSIONER OF CONSERVATION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

Signed R. Barlittan
(TECHNICIAN)

DATE 12-4-84

5772 11-24