

To: 1 047019  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION W/2 SW NW, SEC. 24, T 16 S, R 21  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-22,997-00-00  
3300 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 8572  
Operator: Reach Oil Corp., dba The Reach  
Name & Address Group  
229 E. William, Suite 500  
Wichita, KS 67202

Lease Name Grumbein Well # 1  
County Ness 134.39  
Well Total Depth 4135 Ft. Scott feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 315

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Robert-Gay Energy Enterprises, Inc. License Number 8059  
Address 1006 N. Main, Hutchinson, KS 67501

Company to plug at: Hour: 7:00 pm Day: 27 Month: February Year: 19 86

Plugging proposal received from Dana Hewitt  
(company name) Robert-Gay (phone) 316-669-8164

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2232 KB  
Anhydrite 1503-1539'  
1st plug at 1560' with 50 sx cement

2nd plug at the base of the Cheyenne with 80 sx cement

3rd plug at 345'. with 50 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement  
Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 9:00 pm Day: 27 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1560' with 50 sx cement, 2nd plug at 1190' with 80 sx  
cement, 3rd plug at 345' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug  
at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15  
sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 4 1986

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan.  
(if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita, Kansas

03-04-1986

Signed Paul A. Luthi  
(TECHNICIAN)

( ) did not observe this plugging.

MAR 04 1986

12854

2-27

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 01-17-86 month day year

API Number 15 - 135-22,997-00-00
W. SW NW Sec. 24 Twp. 16 S. Rg. 21 East
3300 Ft. from South Line of Section
4950 Ft. from East Line of Section

OPERATOR: License # 8572
Name Reach Oil Corp., dba The Reach Group
Address 229 E. William, Suite 500
City/State/Zip Wichita, Kansas 67202
Contact Person Jim Gowens
Phone 262-1515

Nearest lease or unit boundary line 330 feet
County Ness
Lease Name Grumbein Well # 1
Ground surface elevation est. 2230 feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Surface pipe by Alternate: 1 2 X
Depth to bottom of fresh water 250'
Depth to bottom of usable water 600'
Surface pipe planned to be set 300'
Projected Total Depth 4100 feet
Formation Cherokee

CONTRACTOR: License # 8059
Name Robert Gay Energy Enterprises, Inc.
City State Hutchinson, Kansas

Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
Gas Inj X Pool Ext Air Rotary
OWWO Expl Wildeat Cable

IF OWWO: old well info as follows:

Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

cementing will be done immediately upon setting production casing.

Date 01-10-86 Signature of Operator or Agent Title Exploration Manager

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 250 feet per ft.
This Authorization Expires 7-13-86 Approved By 7-13-86

spud 2/19/86 set 300' of 8 9/8

did not want plugging orders

PUSHER Dana Hewitt
TD 4135' FORMATION East Aditt
SURFACE PIPE 8 5/8 @ 315'
ANHYDRITE 1529 ELEVATION 2232 MB
STARTING TIME & DATE 2-27-86
COMPLETION TIME & DATE 4:00 pm
1st PLUG @ 1560 FT. W/ 50 SX
2nd PLUG @ 1190 FT. W/ 80 SX
3rd PLUG @ 345 FT. W/ 50 SX
4th PLUG @ 40-0 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY B.G. 60/40 4/6 90/40
TECHNICIAN Hewitt

STATE CORPORATION COMMISSION

MAR 4 1986

CONSERVATION DIVISION
Wichita, Kansas

03-04-1984