

1 070740

10-13

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,935-00-00  
120' W of C  
E/2 E/2 NB SEC. 23, T 16 S, R 21 W/X

3960 feet from S section line

450 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5399

Lease Name Skaggs "A" Well # 2

Operator: American Energies Corporation  
Name & Address: 155 North Market, Suite 710  
Wichita, KS 67202

County Ness 135.20

Well Total Depth 4160 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 606

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor American Energies Corporation License Number 5399

Address 155 North Market, Suite 710, Wichita, KS 67202

Company to plug at: Hour: 2:15 p.m. Day: 13 Month: 10 Year: 1989

Plugging proposal received from Butch Jackson

(company name) American Energies Corporation (phone) 316-793-5088

were: 4 1/2" at 4159' PBTD 4130' Perfs at 4078-31'

1st plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 150 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3 p.m. Day: 13 Month: 10 Year: 1989

ACTUAL PLUGGING REPORT Sand and junk in hole,

1st plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 150 sx cement.

Maximum pressure 1000 psi and shut in 500 psi.

10-19-1989

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 912' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 10-24-89

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 26188  
10-13