

MAY 2 2 1987

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,106-00-00

N/2 NE SE, SEC. 23, T 16 S, R 21 WXX

2310 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5663

Lease Name Skaggs Well # 1

Operator: Hess Oil Company

County Ness 136.83

Name & Address 412 East Douglas, Suite One

Well Total Depth 4210 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 230

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor J.V. Mallard Inc. License Number 4958

Address Box 1009, McPherson, KS 67460

Company to plug at: Hour: 4:30 a.m. Day: 22 Month: 5 Year: 19 87

Plugging proposal received from Jay Snider

(company name) J.V. Mallard Inc. (phone) 316-241-4640

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1513-51'

1st plug at Base Anhydrite with 50 sx cement, 2nd plug at Base Cheyenne with 75 sx

cement, 3rd plug at 30' below base of surface pipe with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:30 a.m. Day: 22 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1551' with 50 sx cement,

2nd plug at 1197' with 75 sx cement,

3rd plug at 260' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.

(If additional description is necessary, use BACK of this form)

RECEIVED STATE CORPORATION COMMISSION

MAY 29 1987

05-29-1987 CONSERVATION DIVISION

INVOICED

DATE 6-2-87

INV. NO. 17086

5-22

Signed Richard W. Lacey (TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date April 3rd 1987
~~March 14~~
month day year

API Number 15- 135-23, 106-00200

OPERATOR: License # 5663
Name Hess Oil Company
Address 412 E. Douglas, Suite One
City/State/Zip Wichita, KS 67202
Contact Person Jamie Hess
Phone (316) 263-2243

N/2 NE SE Sec. 23 Twp. 16 S, Rg. 21 East
231A West
660 Ft. from South Line of Section
660 Ft. from East Line of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 4830 4958
Name J.V. Mallard Drilling Inc
City/State McPherson, Kansas

Nearest lease or unit boundary line 660 feet
County Ness
Lease Name Skaggs Well # 1
Ground surface elevation 2220' feet MSL
Domestic well within 330 feet: no yes no
Municipal well within one mile: no yes no
Surface pipe by Alternate: no yes no
Depth to bottom of fresh water 290' 200'
Depth to bottom of usable water 600' 625'
Surface pipe planned to be set 210'
Projected Total Depth 4150' feet
Formation Cherokee

Well Drilled For: Well Class: Type Equipment:
 Oil SWD Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 3-11-87 Signature of Operator or Agent Jamie Hess Title Geologist

For KCC Use:
Conductor Pipe Required 200 feet; Minimum Surface Pipe Required 40 feet per Alt.
This Authorization Expires 9-24-87 Approved By 3-24-87

Move in 5-14-87

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Arbuckle, if penetratd

1st plug @ more than 50' feet depth with 25 sxs of 60/40 pozmix, 6% gel.
2nd plug @ Anhydrite feet depth with 50 sxs of same
3rd plug @ B/cheyenne feet depth with 75 sxs of same
4th plug @ surf - 30' below surf pipe feet depth with 40 sxs of same
5th plug @ No solid bridge, feet depth with 40 sxs of same
(2) Rathole with circ cement from 40-30' to surf. (b) Mousehole with 10 sxs

PUSHER Jay Snider
TD 4210 FORMATION Miss
SURFACE PIPE 8 3/8 @ 230
ANEHYDRITE 10-13 ELEVATION 224218
STARTING TIME & DATE 4:30 AM
COMPLETION TIME & DATE 6:30 AM
1st PLUG @ 1551 FT. W/ 50 SX
2nd PLUG @ 1197 FT. W/ 75 SX
3rd PLUG @ 260 FT. W/ 40 SX
4th PLUG @ 40 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ 10 SX
WATER WELL PLUGGED W/ 10 SX
CEMENT COMPANY B.S. Titus
TECHNICIAN

60/40 6% gel

RECEIVED
STATE CORPORATION COMMISSION

MAY 29 1987
05-29-1987
CONSERVATION DIVISION
Wichita, Kansas