

1 031117

10-27

API NUMBER 15- 135-23,509--00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App.
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SW NW, SEC. 19, T 16 S, R 21 W/K

2970 feet from S section line

4310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Lease Name Walker "J" Well # 2

Operator: Petroleum, Inc.

County Ness 143.16

Name & Address 301 N. Main, Suite 900

Well Total Depth 4405 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 298

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Allen Drilling Company License Number 5418

Address 7950 E. Prentice, #100, Englewood, CO 80111

Company to plug at: Hour: 8:30 a.m. Day: 27 Month: 10 Year: 19 90

Plugging proposal received from R.G. Julius

(company name) Allen Drilling Company (phone) 316-793-5681

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1644'

1st plug at 1650' with 50 sx cement, 2nd plug at 800' with 80 sx cement,

3rd plug at 320' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 2:30 p.m. Day: 27 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 1650' with 50 sx cement,

2nd plug at 800' with 80 sx cement,

3rd plug at 320' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-6-90

INV. NO. 29838

10-30-1990
CONSERVATION DIVISION
Wichita, Kansas

Signed Steve [Signature] (TECHNICIAN)

EFFECTIVE DATE: 10-1-90

State of Kansas 15 135-23,509 00-00

NOTICE OF INTENTION TO DRILL
Must be approved by the K.C. five (5) days prior to commencing well

Expected Spud Date October 2 1990
month day year

APP SE SW NW Sec 19 Twp 16 S, Rg 21 East West

OPERATOR: License # 5238
Name: Petroleum, Inc.
Address: 301 N. Main, Suite 900
City/State/Zip: Wichita, KS 67202
Contact Person: Everett Jones
Phone: 913 434-4647

2970
4310 feet from South line of Section
feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License # 4958 5413
Name: J.V. Mallard Inc. Allen Dring

County: Ness
Lease Name: Walker 'J' Well #: 2
Field Name: _____

Well Drilled For: Well Class: Type Equipment:
 Oil ... Inj ... Infield Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OILW ... Disposal Wildcat ... Cable
... Seismic; ... # of Holes

Is this a Prorated Field? yes no
Target Formation(s): Cherokee/Ft. Scott
Nearest lease or unit boundary: 330
Ground Surface Elevation: 2319 feet MSL

If O.W.O.: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Domestic well within 330 feet: yes no
Municipal well within one mile: yes no
Depth to bottom of fresh water: 100'
Depth to bottom of usable water: 680'
Surface Pipe by Alternate: 1 2

Directional, Deviated or Horizontal wellbore? yes no
If yes, total depth location: _____

Length of Surface Pipe Planned to be set: 275'
Length of Conductor pipe required: 0
Projected Total Depth: 4350'
Formation at Total Depth: Mississippi

Exp. 3/26/91

AFFIDAVIT

250' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher R. J. Julius
SPUD DATE 10-20-90 INIT. DR
LENGTH SURFACE PLANNED 298' - KB 1800' cc.

RESERVE PIT STATUS - REMOVE FLUID _____ LINED _____
after salt sect. _____ bbls. when done _____ bbls.

RATHOLE AHEAD? Y N SIZE HOLE _____
SURFACE PIPE 8 3/8" @ 298' CONDUCTOR _____
ANHYDRITE T- 16 1/4" B- _____ ELEVATION _____
TD 4405 FORMATION MISS

RAN PIPE @ _____ DV TOOL _____ ALT II DONE _____
_____ SX _____ Y _____ N _____

10-30-1990
CONSERVATION DIVISION
Wichita, Kansas
Arbuckle Plug @ _____ Ft. W/ _____ SX
Aug./Council @ _____ Ft. W/ _____ SX
Anhydrite Base @ 1650 Ft. W/ 50 SX

1/2 Base Anyh. @ 800 Ft. W/ 80 SX
1/2, 1/2 Plug @ 320 Ft. W/ 40 SX
Bottom Surface @ 40 Ft. W/ 10 SX
40' Plug @ _____ Ft. W/ _____ SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX
WATER WELL _____ SX (Irr. Well _____ Pond _____)
Hauling _____

TECHNICIAN R.L. DATE 10-25-90
TYPE OF CEMENT 60/40 4% gel

STARTING TIME 5:30 (AM/PM) DATE 10-27-90
COMPLETION TIME 2:30 (AM/PM) DATE 10-27-90

CEMENT COMPANY B.G.