

TYPE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # _____ EXPIRATION DATE _____

OPERATOR Kimbark Oil & Gas Company API NO. 15-135-22,251-00-00

ADDRESS 1580 Lincoln St., Ste. 700 COUNTY Ness

Denver, Colorado 80203 FIELD Wildcat

** CONTACT PERSON C. A. Hansen PROD. FORMATION _____

PHONE 303/839-5504

PURCHASER _____ LEASE Elmore

ADDRESS _____ WELL NO. 1

DRILLING CONTRACTOR Murfin Drilling Company 1980 Ft. from West Line and

ADDRESS 617 Union Center Bldg. 660 Ft. from South Line of

Wichita, KS 67202 the SW (Qtr.) SEC 2 TWP 17S RGE 21W.

PLUGGING As above WELL PLAT _____ (Office Use Only)

CONTRACTOR _____

ADDRESS _____

TOTAL DEPTH 4135' PBTD _____

SPUD DATE 6/8/82 DATE COMPLETED 6/16/82

ELEV: GR 2179' DF 2181' KB 2184'

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE _____

Amount of surface pipe set and cemented 438' DV Tool Used? No

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other _____

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

C. A. Hansen, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.


C. A. Hansen (Name)

Subscribed and sworn to before me this 2nd day of July



Christian Puckert (NOTARY PUBLIC)

MY COMMISSION EXPIRES: SEPTEMBER 15, 1982



** The person who can be reached by phone regarding any questions concerning this information.

OPERATOR Kimbark Oil & Gas Co LEASE Elmore

SEC. 2 TWP. 17SRGE. 21W

FILL IN WELL LOG AS REQUIRED: Well #1

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
surface soil & clay	0	354	Heebner	3604 (-1420)
Shale	354	439	Lansing	3650 (-1466)
shale & sand	439	981	Base Kansas City	3954 (-1770)
anyhdrite	981	1494	Pawnee	4008 (-1824)
shale	1494	1884	Ft. Scott	4102 (-1918)
shale & lime	1884	3600	Cherokee Sh.	4114 (-1930)
lime	3600	3720	Cherokee SD.	4126 (-1942)
lime & shale	3720	3936		
lime	3936	3988		
lime & chert	3988	4070		
lime	4070	4135		

Report of all strings set— surface, intermediate, production, etc. CASING RECORD (New) or ~~Used~~

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Socks	Type and percent additives
Surface	12-1/4	8-5/8	24#	438	Common	300	3% c.c.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Socks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

Date of first production Dry	Producing method (flowing, pumping, gas lift, etc.)	Gravity
---------------------------------	---	---------

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water %	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold)	Perforations
--	--------------