

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

AUG 7 1962

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Aladdin Pet Corp
Complete Address: 809 Pet Bldg Wichita, Kansas
Lease Name Brecklein Well No. 1
Location CNW SE Sec. 30 Twp. 17 Rge. (E) (W) 25
County Ness Total Depth 4624
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Glenn & Smith
Address: Ellinwood, Kansas License No. 396
Operation Completed: Hour 10AM Day 4 Month 8 Year 62

The Above well was plugged as follows:

8 5/8" 278' circulated with cement - 5 1/2" 4488' with 150 sax cement-
Baker plug at 4472' - perforated 4428'.
Filled with sand to 4400', set 4 sax cement with dump bailer, pulled 5580'
5 1/2" - filled with heavy pit mud to 600', set 20 sax cement at 600', heavy
pit mud to 170', set 20 sax cement at 170', heavy pit mud to 55', set 10 sax
cement to bottom cellar.

I hereby certify that the above well was plugged as herein stated.

8/7/62
5496-w

Signed: [Signature]
Well Plugging Supervisor