

KANSAS

Form CP-3
Rev. 6-4-68

R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 16 1978

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135 - 21,523 - 0000 (of this well)

Operator's Full Name Kansas Oil Corp.

Complete Address 400 N. Woodlawn, Suite 2, Wichita, Kansas

Lease Name Norton-Reed "B" Well No. 3

Location NW SE Sec. 29 Twp. 17 Rge. (E) (W) 25

County Ness Total Depth 4440'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Warrior Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 5 A Day 7 Month 10 Year 1978

The above well was plugged as follows:

RTD 4440' 8 5/8 csg set 251' cwc 180 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 720' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo Massey
Well Plugging Supervisor

DATE 10-12-78
INV. NO. 8271-4