

15-135-20910-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 1 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Boron Corporation

Complete Address 1130 Vickers KSB&T Bldg., Wichita, Kansas

Lease Name Popp Well No. 1

Location C NE NW Sec. 29 Twp. 17 Rge. (E) (W) 25

County Ness Total Depth 4440'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Gabbert-Jones Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 8:30 A Day 29 Month 6 Year 1974

The above well was plugged as follows:

RTD 4440' 8 5/8 csg set at 245' cwc 160 sk. Cmt. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 215' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo E. Mansley
Well Plugging Supervisor

DATE 7/2/74

INV. NO. 9428-W