

15-135-20697-0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

10 25 1972

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Pickrell Drilling Company,

Complete Address 705 Fourth National Bank Building, Wichita, Kansas.

Lease Name Norton-Reed Well No. A-1

Location CNW-SW Sec. 29 Twp. 17 Rge. (E) (W) 25

County Ness Total Depth 4468'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 2:00 PM Day 22 Month 10 Year 1972

The above well was plugged as follows:

258'--8 5/8" Surface casing, cement circulated with 140 Sx.
Top of Dakota section C 500'.

Circulated hole with heavy mud. Pulled DP to 725' and displac'd 110 Cu. Ft. cement
thru DP from 725' to 400'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge O 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: N. L. Dinkel
Well Plugging Supervisor

DATE 10/27/72
INV. NO. 6526-44