

15-135-19090-0000

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 132 - 21 County: Ness

Location: SE SE SE Sec. 28 Twp. 17 Rge. 25 (E) (W)

Name of Field: Reed Total Depth: 4344

I have this date completed supervision of plugging of:

Lease Name: Reed G Well No. 1

Operator's Full Name: Magnolia Pet Co

Complete Address: Box 770 Great Bend, Kansas

Plugging Contractor: West Supply

Address: Chase, Kansas License No. 14

Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes No

If yes how long? _____ Reason: _____

Operation Completed: Hour 7pm Day 28 Month Oct Year 1958

The above well was plugged as follows:

TD-4344 8 5/8" set at 250' cwc 5 1/2" set at 4336'

Checked hole to 4352' and found it open. Filled w/sand to 4335' and dumped 5 sax cement with bailer. Pulled two joints of 5-1/2" casing. Hooked up cir-pump and circulated casing with 20 sax of gel mud at 550' and pumped in 20 sax of cement at 550'. Pulled pipe to 240' and pumped in 20 more sax cement. pulled rest of casing, and cleared hole and mudded to 40' set a 10' rock bradge and ram 19 sax cement to base of cellar,

Signed: Gilbert P. Leiker
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

PLUGGING
FILE SEC 28 T. 17 R. 25W
BOOK PAGE 132 LINE 21

RECEIVED
STATE CORPORATION COMMISSION
NOV 12 1958
CONSERVATION DIVISION
WICHITA, KANSAS