

15-135-20421-00-00

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

SEP 5 1972

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Palomino Petroleum

Complete Address 304 Insurance Building, Wichita, Kansas 67202

Lease Name Shearer Well No. 1

Location N/2 NE NE Sec. 27 Twp. 17 Rge. (E) (W) 25

County Ness Total Depth 4489'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Ralph Glenn

Address Box 156 Ellinwood, Kansas 67526 License No. 396

Operation Completed: Hour 3:15 P Day 29 Month 8 Year 1972

The above well was plugged as follows:

Total Depth 4489' 8 5/8 csg set at 240' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.

5 1/2 csg set at 4418' cw 100 sk cmt.

Filled 5 1/2 csg W/sd (4400-4489) Dumped 5 sk cmt W/dump bailer. (4365-4400)

Cutoff and recovered 1491' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, -70 sk cmt, -10 sk gel & water, -released 8 5/8 plug and pumped 50 sk cmt. PP 400 lbs. SI pres. 150 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

9/5/72

INV. NO.

6273-11

Signed:

Booth Massey
Well Plugging Supervisor