

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

FILED
STATE
DEC 9 1959
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Wessex County
Location: Sec. 27 Twp. 17 Rge. 25 (E) (W)
Name of Field: _____ Total Depth: 4515

I have this date completed supervision of plugging of:

Lease Name: Larise E. Ewert Well No. 1
Operator's Full Name: Magnolia Pet. Co.
Complete Address: Box 770 Mt Bend, Kansas
Plugging Contractor: Ace Pipe Pulling Co.
Address: Mt Bend, Kans. License No. 2
Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 3pm Day 2 Month Dec Year 1959

The above well was plugged as follows:

Total Depth - 4515 - 9 7/8" set at 249' - 5 1/2" at 4515 - Perf. 4446
Sand to 4430' and displaced 5 sack cement with dump barrels
shot 5 1/2" pipe at 3000' and pulled same to 600' hooked
pump truck to 5 1/2" pipe and circulated mud to bottom of cellar,
displaced 20 sack cement thru 5 1/2" with pump truck at
600', pulled pipe to 240', and displaced 20 sack cement, pulled
pipe out of hole, built solid rock bridge at 40' and displaced
10 sack cement, cementing to base of cellar.

Signed: Gilbert G. Leiker
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

INVOICED

DATE 1/14/60
INV. NO. 682-w