

10
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 8 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Sunray D-X Oil Co
Complete Address: Box 729 Great Bend, Kansas
Lease Name Schaben Well No. 1
Location CNE NE Sec. 25 Twp. 17 Rge. (E) (W) 25
County Ness Total Depth 4525
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractors: Steckel Drg Co & Halliburton Co
Address: Great Bend, Kansas License No.
Operation Completed: Hour 11PM Day 1 Month 4 Year 63

The Above well was plugged as follows:

8 5/8" 279' circulated with cement.

Circulated hole with heavy mud, set plug at 500', 1/4 sack hulls and 25 sax cement displaced through drill pipe, heavy mud to 270', set plug 1/4 sack hulls and 25 sax cement displaced through drill pipe, heavy mud to 40', set plug, 1/2 sack hulls and filled to bottom cellar with cement.

Cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

NOTICED
DATE 4/8/63
INV. NO. 6868-W

Signed: *Edna Kelly*
Well Plugging Supervisor