

15-135-20333-00-00

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 3 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Hummon Oil, Inc.

Complete Address 821 Union Nat'l Bldg., Wichita, Kansas 67202

Lease Name Potter Well No. 1

Location C NE SW Sec. 25 Twp. 17 Rge. (E) (W) 25

County Ness Total Depth 4450'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co.

Address Box 105 Chase, Kansas License No. 436

Operation Completed: Hour 2:30 P Day 28 Month 4 Year 1971

The above well was plugged as follows:

Total Depth 4450' 8 5/8 csg set at 280' cwc

5 1/2 csg set at 4435 cw 100 sk cmt.

5 1/2 csg PBTD 4390' with perf. (4386-4388)

Filled 5 1/2 csg W/sd (4375-4390) Dumped 5 sk cmt w/dump bailer. (4340-4375)

Recovered 2400' of 5 1/2 csg.

Pumped down 8 5/8 csg with 30 sk gel w/3 sk hulls -100 sk 6% poz -12 bbl. water -

release plug and pumped 20 sk 6% poz. Max. pres. 500 lbs. SI pres. 250 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Paul Massey
Well Plugging Supervisor

DATE 5/3/71

INV. NO. 3042-11