

15-135-00511-00-00

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

JAN 31 1964

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Barnett Oil Co

Complete Address: 411 1st Natl Bk Wichita, Kansas

Lease Name Potter Well No. 2

Location QW 1/2 SW NW Sec. 25 Twp. 17 Rge. (E) (W) 25

County Ness Total Depth 4447

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Forbes Casing Pulling & Halliburton Co

Address: Great Bend, Kans License No. \_\_\_\_\_

Operation Completed: Hour 8PM Day 29 Month 1 Year 64

The Above well was plugged as follows:

8 5/8" 220' circulated with cement - 5 1/2" 4447' with 125 sax cement.  
PB to 4370' - perforated 4316'

Filled with sand to 4300', set 4 sax cement with dump bailer - pulled  
3000' 5 1/2" to 600', circulated hole with heavy mud through 5 1/2" at 600'  
(40 sax Gel), displaced 20 sax cement through 5 1/2" at 600', heavy mud to  
200 - displaced 20 sax cement through 5 1/2" at 200', heavy mud to 35' -  
cement to 0'.

Mudding and cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

INDEXED

Signed: [Signature]  
Well Plugging Supervisor

DATE 1/31/64

INV. NO. 8565-11