

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-135-21, 664-00-00

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name JOHN J DARRAH.

Complete Address 1010 CENTRY PLAZA BLDG, WICHITA, KANS. 67202

Lease Name SCHABEN Well No. 5#1

Location C-NE-SE Sec 24 Twp. 17 Rge. 25 (East) (West)

County NESS Total Depth 4390 ^{FE}

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor WELSO CASING PULLING

Address BOX 176 CHASE, KANS. License No. _____

Operation Completed: Hour: 4:05 PM Day: 4th Month: SEPT Year: 1981

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

8 5/8" - 298^{FE} SB. CULG ^{1/190ST} CMT. \rightarrow 5 1/2" SET @ 4388^{FE} ^{1/140ST} CMT.

PERF'S OPEN HOLE 2^{FE}, SAND BOTTOM TO 4320^{FE} ^{1/5ST} CMT.

SHOT PIPE 5 TIMES RECOVERED 1510^{FE}

ORDERED 140ST 5/50 PERMIX 4% GEL - 3% CA-CL. \rightarrow 20ST GEL,

3ST HALL'S. + 8 5/8" PLUG. \rightarrow PUMPED IN 8 5/8" WITH PUMP. TRUCK.

PUT. IN - 2ST HALL'S - 12ST GEL. \rightarrow 1ST HALL'S \rightarrow 70ST CMT.

8ST GEL. \rightarrow RELEASED PLUG. AND 70ST CMT.

MAX. PRESSURE 800 LBS

STATE RECEIVED
CONSERVATION COMMISSION
SEP - 8 1981
CEMENTED BY ALLIED

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: T. Galt
Conservation Division Agent
Wichita, Kansas

DATE 10-28-81

NO. 8078 W