

15-135-60134-00-00

Form CP-3
Rev. 6-4-68

KANSAS

AP
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 17 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Forbes & Reeves

Complete Address P. O. Box 681 Great Bend, Kansas 67530

Lease Name Schaberr Well No. 1

Location SW NW SE Sec. 24 Twp. 17 Rge. (E) (W) 25

County Ness Total Depth 4420'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698 Great Bend, Kansas License No. 670

Operation Completed: Hour 1:45 PM Day 11 Month 10 Year 1972

The above well was plugged as follows:

Total Depth 4420' 9 5/8 csg set at 276' cwc 150 sk.

5 1/2 csg set at 4419' cw 200 sk cmt.

5 1/2 csg PBTD 4383' with top perf. (4263')

Filled 5 1/2 csg W/sd (4240-4383) Dumped 5 sk cmt W/dump bailer. (4205-4240)

Cutoff and recovered 2500' of 5 1/2 csg.

Pumped down 9 5/8 csg with 20 sk gel & water W/300 lbs hulls, - 70 sk cmt - 10 sk

gel & water - released 9 5/8' plug and pumped 60 sk cmt . Maximum pump-in pressure-

-500#. Final Shut-in Pressure-250#. (Mudding and Cementing by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Dickels*
Well Plugging Supervisor

INDEXED
DATE 10/17/72
INV. NO. 6493-W