

15-135-19088-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 1 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Company

Complete Address 705 4th Nat'l Bk. Bldg., Wichita, Kansas 67202

Lease Name Stutz "A" Well No. 1

Location C SE NW Sec. 18 Twp. 17 Rge. (E) (W) 25

County Ness Total Depth 4510'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling Inc.

Address Box 1082 Great Bend, Kansas License No. 623

Operation Completed: Hour 2P Day 29 Month 9 Year 1969

The above well was plugged as follows:

Total Depth 4510' 8 5/8 csg set at 256' cwc 170 sk.

5 1/2 csg set at 4509' cw 100 sk cmt.

5 1/2 csg perf. (4450-4457)

Filled 5 1/2 csg w/sd (4400-4509) Dumped 5 sk cmt w/dump bailer. (4360-4400)

Cutoff and recovered 1520' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel w/4 sk hulls, 70 sk cmt., 7 sk gel, 1 sk hull and 60 sk cmt.

Cmt. (0-250) Gel. (250-600) Cmt (600-900) Gel (900-TD)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo P. Messing
Well Plugging Supervisor

DATE 10/1/69

INV. NO. 563-W