

KANSAS

FORM CP-3  
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-135-20, 654-00-00

200 Colorado Derby Bldg.  
Wichita, KS 67202

Operator's Full Name PICKRELL DRILLING COMPANY

Complete Address 205 LITWIN BLDG. WICHITA, KANS. 67202

Lease Name NORTON Well No. #2 - "KE"

Location SE-SE Sec. 18 Twp. 17 Rge. 25 (East) (West)

County NESS Total Depth 4497 <sup>FE</sup>

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor HELSO CASING PULLING

Address BOX 176 CHASE, KANS. License No. 683

Operation Completed: Hour: 12:30 <sup>PM</sup> Day: 10 <sup>th</sup> Month: SEPT Year: 1981

Plugging Operations attended by Agent? All  Part  None

The above well was plugged as follows:

8 5/8" - 218 <sup>FE</sup> SB CML 1/150 <sup>ST</sup> CONT → 5 1/2" SET @ 4482 <sup>FE</sup> 1/160 <sup>ST</sup> CONT.  
DEEP'S OPEN HOLE 15 <sup>FE</sup> - ON BOTTOM - COULDN'T GET DOWN → MUD @ 2750 <sup>FE</sup>  
5 1/2" SQUEEZED @ 1398 <sup>FE</sup> 1/150 <sup>ST</sup> CONT.  
SHOT 3 - TIMES - RECOVERED - 765 <sup>FE</sup>  
ORDERED 180 <sup>ST</sup> 50 <sup>POZ</sup> MIX 6% GEL. → 10 <sup>ST</sup> GEL → 3 <sup>ST</sup> HULL'S + 8 5/8" PLUG.  
PUMPED IN 8 5/8" WITH PUMP TRUCK.  
PUT. IN → 100 <sup>ST</sup> CONT. → 10 <sup>ST</sup> GEL → 2 <sup>ST</sup> HULL'S. → RELEASED PLUG.  
AND 80 <sup>ST</sup> CML. → MAX PRESSURE 700 <sup>PSI</sup>  
CEMENTED BY FULLED CML.

I hereby certify that the above well was plugged as herein stated.

RECEIVED

SEP 11 1981

Signed: Martin Schmidt  
Conservation Division Agent  
J. Steve Dewart

DATE 10/6/81  
FILE NO. 7820-W

CONSERVATION DIVISION  
Wichita, Kansas