

15-135-20328-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

*JP*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 2 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Company

Complete Address 1130 Vickers KSBT Bldg. Wichita, Kansas 67202

Lease Name Stutz Well No. 1

Location C NE NW Sec. 18 Twp. 17 Rge. (E) (W) 25

County Ness Total Depth 4480

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Strata Drlg.

Address Wichita, Kansas License No.       

Operation Completed: Hour 2A Day 31 Month 3 Year 1970

The above well was plugged as follows:

RTD 4480' 8 5/8 csg set at 286' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Ben F. M...e  
Well Plugging Supervisor

INVOICED

DATE - 4/2/70  
INV. NO. 1675-4