

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUN 18 1963

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Leo J. Dreiling Oil Co 15-051-04312-00-00

Complete Address: Victoria, Kansas

Lease Name Weisner Well No. 1

Location CS $\frac{1}{2}$ SE SE Sec. 26 Twp. 13 Rge. (E) (W) 20

County Ellis Total Depth 3830

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Ace Pipe Pulling

Address: Great Bend, Kans License No. 2

Operation Completed: Hour 9:30AM Day 15 Month 6 Year 63

The Above well was plugged as follows:

8 5/8" 220' circulated with cement - 5 1/2" 3819' with 100 sax cement.
Filled with sand to 3800', set 4 sax cement with dump bailer - pulled
3004' 5 1/2" to 550', circulated hole with heavy gel mud - displaced
20 sax cement through 5 1/2" at 550', heavy mud to 200', displaced 20
sax cement through 5 1/2" at 200', heavy mud to 35', set bridge and filled
to bottom cellar with cement.

Cementing and mudding by Ace Pipe Pulling pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/18/63

INV. NO. 7284-W

Signed: Edson Kelly
Well Plugging Supervisor