

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -051-21315-0000 (of this well)

Operator's Full Name R. A. COMEAU OIL COMPANY
Complete Address 311 SOUTH JEFFERSON - PLAINVILLE, KANS. 67663
Lease Name KRAUS Well No. #4
Location SE-SE-SE Sec. 26 Twp. 13^S Rge. 20 (E) (W)
County ELLIS Total Depth 3884 FE
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____

Plugging Contractor HELSO CASING. PULLING
Address BOX 176 CHASE, KANS. 67524 License No. 683
Operation Completed: Hour 10:15 AM Day 22ND Month MAY Year 1980

The above well was plugged as follows:

8 5/8" 208 FE SP. CUC. w/140^{SE} CMT. -> 5 1/2" SET AT 3883 FE w/125^{SE} CMT.
PLUG. BACK 3867 FE -> PERFS - 3828 FE - 3200 FE
BOTTOM PLUG. SAND TO 3150 FE AND 5^{SE} CMT. SHOT PIPE AT 3107 FE
RECOVERED 3107 FE
ORDERED 140^{SE} 50^{SE} PORMIX 6% GEL - 19^{SE} GEL -> 6^{SE} HULL'S + 8 5/8" PLUG.
PUMPED IN 8 5/8" WITH PUMP TRUCK.
PMT IN 3^{SE} HULL'S -> 12^{SE} GEL -> 70^{SE} CMT. -> 7^{SE} GEL -> 3^{SE} HULL'S
RELEASED PLUG. AND 70^{SE} CMT. MAX PRESSURE 495^{PSI}

CEMENTED BY ALLIED CMT.

I hereby certify that the above well was plugged as herein stated.

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

Signed: M. J. Schmidt
Well Plugging Supervisor

DATE 5-20-80

MAY 23 1980

INV. NO. 2251-W

CONSERVATION DIVISION
Wichita, Kansas