

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

STATE CORPORATION COMMISSION
DEC 11 1959
CONSERVATION DIVISION
WICHITA, KANSAS

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis 30633
15:DS1:00709:00:00
Location: SW NW NE Sec. 26 Twp. 13 Rge. 20 (E) (W)
ANB KC
Name of Field: _____ Total Depth: 3810

I have this date completed supervision of plugging of:
Lease Name: Herman Well No. 2
Operator's Full Name: Burch Drg Co
Complete Address: 1011 Union Center Wichita, Kans
Plugging Contractor: Knight Casing Pulling
Address: Great Bend, Kans License No. 436
Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____
Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No
If yes how long? _____ Reason: _____

Operation Completed: Hour 2PM Day 7 Month 12 Year 59

The above well was plugged as follows:
8 5/8" 225' circulated with cement - 4 1/2" 3809' with 125 sax cement behind
Perforated 3600'. set plugs and sand to 3470', set 3 sax cement with dump
bailer, pulled 3200' 4 1/2" to 600', circulated hole with heavy mud through 4 1/2"
at 600' (26 sax Gel), displaced 20 sax cement through 4 1/2" at 600', heavy mud
to 200', displaced 20 sax cement through 4 1/2" at 200', heavy mud to 35', set
bridge and 10 sax cement to bottom cellar.
Mudding and cementing by Knight Casing pulling Co. pump truck.

Signed: E. Don Petty
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

INVOICED
DATE 1/14/60
INV. NO. 548-w