

R

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

1-24-77

API Number 15 -051 -21,273-0000 (of this well)

Operator's Full Name Black-Stem Investors of Hays

Complete Address Catherine RT. Box 39, Hays, Kansas

Lease Name Herman Est. Well No. 2

Location 330' FWL & 660' FNL of NE/4 Sec. 26 Twp. 13 Rge. (E) (W) 20

County Ellis Total Depth 3812'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Helberg Drlg.

Address Morland, Kansas License No.       

Operation Completed: Hour 11 P Day 21 Month 1 Year 1977

The above well was plugged as follows:

RTD 3812' 8 5/8 csg set 211' cwc 150 sx. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 660' thru drill pipe.

Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Leo Massey  
Well Plugging Supervisor

DATE 1-24-77  
4515-W