

To: 1000004
STATE CORPORATION COMMISSION
Wichita-State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 135-20,781-00-00
150' S
of NW NE, SEC. 12, T. 17 S, R. 21 W/E

TECHNICIAN'S PLUGGING REPORT

7-19

Operator License # 5363
Operator: BEREXCO Inc.
Name & Address P.O. Box 723
Hays, KS 67601

4470 feet from S section line
1980 feet from E section line
Lease Name Meehan Well # 2A
County Ness 133.90
Well Total Depth 4120 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 437

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor BEREXCO, Inc. License Number 5363
Address P.O. Box 723, Hays, KS 67601

Company to plug at: Hour: 9 a.m. Day: 19 Month: 7 Year: 19 96

Plugging proposal received from Ted Crawford
(company name) BEREXCO, Inc. (phone) 913-628-6101

were: 5 1/2" at 4119' w/175 sx cement, PBSD 4090', Perfs at 4042-46, 4056-60, 4050-54'
1st plug pump 300 lbs. hulls, 50 sx cement, gel to 800'

RECEIVED
KANSAS CORPORATION COMMISSION

2nd plug perforate at 800' and fill to surface with cement.

Pump 175 sx cement down backside.

JUL 23 1996
07-23-1996
CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by Bill Johnson (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:45 a.m. Day: 19 Month: 7 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug pumped 300 lbs. hulls, 50 sx cement, 33 sx gel spacer to 800'

2nd plug Mercury perforated at 800', pumped 150 sx cement. Maximum pressure 1000 psi and shut in 200 psi on 5 1/2"

3rd plug pumped down 8 5/8" with 25 sx cement. Pressured up to 500 psi.

4th plug perforated at 430' and pumped down 5 1/2" with 50 sx cement. Circulated cement to surface. Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 7-24-96
INV. NO. 46078
observe this plugging.

Signed Klein D Strub (TECHNICIAN)