

To: 1 040494
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-23,526-00-00
NW NE SW, SEC. 7, T 17 S, R 21 (W)E

TECHNICIAN'S PLUGGING REPORT

2150 feet from S section line
3710 feet from E section line

Operator License # 3321

Lease Name Yawger Well # H-2

Operator: Hoffman Petroleum Inc

County Ness 143.03

Name & Address: 1600 Broadway Suite 1210
Denver, CO 80202

Well Total Depth 4401 Miss feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 240

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Co. License Number 5302

Address 1720 KSB&T Bldg Wichita, KS 67202

Company to plug at: Hour: 7:00 Day: 12 Month: December Year: 1990

Plugging proposal received from Terb Ogle

(company name) Red Tiger Drilling (phone) 316-263-2371

Work: Fill hole with drilling mud + spot plugs through
drill pipe. 1st plug @ 1700' w/50sx, 2nd plug @
900' w/80sx, 3rd plug @ 500' w/50sx, 4th plug @
270' w/40sx, 5th plug @ 40' w/10sx 6th plug fill
rathole w/15sx

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 9:00 pm Day: 12 Month: December Year: 1990

ACTUAL PLUGGING REPORT Filled hole with drilling mud + spotted plugs
through drill pipe 1st plug @ 1700' w/50sx, 2nd plug @
900' w/80sx, 3rd plug @ 500' w/50sx, 4th plug @
270' w/40sx, 5th plug @ 40' w/10sx, 6th plug fill
rathole w/15sx

STATE CORPORATION COMMISSION
12-16-1990
DEC 16 1990

Remarks: Halliburton pumped 60/40 pozmix 6% acf
INVOICED (if additional description is necessary, use BACK of this form. WICHTA, KANSAS)

I (did / did not) observe this plugging.

DATE JAN 09 1991

QIV. NO. 30423

12-12

Signed Stephen J. Pfeifer
(TECHNICIAN)