

To: 1 080017
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-14 144 R
API NUMBER 15-135-23,417-00-00
100' W of
NE SW NW, SEC. 6, T 17 S, R 21 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123
Operator: Pickrell Drilling Company, Inc.
Name & Address: 110 North Market, Suite 205
Wichita, KS 67202

3630 feet from S section line
4390 feet from E section line

Lease Name Albers Well # 1-D
County Ness 139.85
Well Total Depth 4303 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 321

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Pickrell Drilling Company, Inc. License Number 5123
Address 110 North Market, Suite 205, Wichita, KS 67202

Company to plug at: Hour: 1 a.m. Day: 14 Month: 1 Year: 19 90

Plugging proposal received from Doyle Folkerts
(company name) Pickrell Drilling Company, Inc. (phone) 316-262-8427

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1566'
1st plug at 1560' with 50 sx cement, 2nd plug at 880' with 80 sx cement,
3rd plug at 350' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Mike Spain (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:15 a.m. Day: 14 Month: 1 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 1560' with 50 sx cement,
2nd plug at 880' with 80 sx cement,
3rd plug at 350' with 40 sx cement,
4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 1-29-90
INV. NO. 27225

Signed Mike Spain (TECHNICIAN)

EFFECTIVE DATE: 1-22-90

State of Kansas 15-135-23,417-00-00

FORM MUST BE SIGNED ALL BLANKS MUST BE FILLED

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 1 6 90 month day year

100' W of NE SW NW Sec 6 Twp 17S S, Rg 21 East West

OPERATOR: License # 5123 Name: Pickrell Drilling Company, Inc. Address: 110 N. Market, Suite 205 City/State/Zip: Wichita, KS 67202 Contact Person: Jay McNeil Phone: 262-8427

3630 feet from South line of Section 4390 feet from East line of Section (Note: Locate well on Section Plat Below)

CONTRACTOR: License #: 5123 Name: Company Tools

County: Ness Lease Name: Albers Well #: 1-D Field Name: Unknown

Well Drilled For: Well Class: Type Equipment: Oil Inj Infield Mud Rotary Gas Storage Pool Ext Air Rotary Disposal Wildcat Cable

Is this a Prorated field? yes X no Target Formation(s): Cherokee-Miss Nearest lease or unit boundary: 990' Ground Surface Elevation: 2265 feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Depth to bottom of fresh water: 160' Depth to bottom of usable water: 900' Surface Pipe by Alternate: 1 X 2 Length of Surface Pipe Planned to be set: 300'+ Length of Conductor pipe required: None Projected Total Depth: 4350' Formation at Total Depth: Mississippi Water Source for Drilling Operations: well farm pond X other

If CADO: old well information as follows: Operator: Well Name: Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no If yes, total depth location:

DWR Permit #: N/A Will Cores Be Taken? yes X no If yes, proposed zone:

set 300+ of 8 3/8 on 1-9-89 300' Alt. II Req.

Exp. 6/28/90

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will

PUSHER Doyle Faulkner TD 4303 FORMATION M.S.S SURFACE PIPE 8 3/8 @ 321 ANHYDRITE 1566 ELEVATION STARTING TIME & DATE 1:00 AM COMPLETION TIME & DATE 4:15 AM 1-14-90 1st PLUG @ 1560 FT. W/ 50 SX 2nd PLUG @ 880 FT. W/ 80 SX 3rd PLUG @ 350 FT. W/ 40 SX 4th PLUG @ 40-0 FT. W/ 10 SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ SX WATER WELL PLUGGED W/ SX CEMENT COMPANY ALLIED TECHNICIAN Hurs - McMillen TYPE OF CEMENT 60/40 670

STATE OF KANSAS CONSERVATION DIVISION JAN 17 1990 01-17-1990

Table with 10 columns and 10 rows of depth markers (5250 to 330).

Wichita, Kansas

- REMEMBER TO: File Drift Pit Application (form CDP-1) with Intent to Drill; File Completion Form ACU-1 within 120 days of spud date; File acreage attribution plat according to field prorated orders; Notify appropriate district office 48 hours prior to workover or re-entry; Submit plugging report (CP-4) after plugging is completed; Obtain written approval before disposing or injecting salt water.