

To: 1 302030
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
136 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 135-23,929-00-00
C NE NE, SEC. 19, T 17 S, R 21 W/2
4620 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 6668

Lease Name Wolfe Well # 1

Operator: Leben Corporation

County Ness 142.02

Name:
Address 105 S. Broadway, Ste. 640
Wichita, KS 67202

Well Total Depth 4370 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Co., Inc. License Number 5929

Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: _____ Day: 20 Month: 4 Year: 19 96

Plugging proposal received from Rich Wheeler

(company name) Duke Drilling Co., Inc. (phone) 316-267-1331

was: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1553-85'

1st plug at Arbuckle with 50 sx cement, 2nd plug at 1580' with 50 sx cement,

2nd plug at 680' with 80 sx cement, 3rd plug at 290' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1 p.m. Day: 20 Month: 4 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug at 1580' with 50 sx cement,

2nd plug at 680' with 80 sx cement,

3rd plug at 290' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

I (TWO) (did not) observe this plugging.

Signed Richard W. Lacey
(TECHNICIAN)

DATE MAY 27 1996

WICH. REG. 45585 4-20 JUN 27 1995

EFFECTIVE DATE: 4-10-96

State of Kansas

15-135-23,929-00-00

FORM MUST BE TYPED

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

DISTRICT # 1

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well.

SGA? Yes [X] No

Expected Spud Date April 8, 1996

Spot C NE NE Sec 19 Twp 17S S, Rg 21W East West

OPERATOR: License # 6668
Name: LFBN CORPORATION
Address: 105 South Broadway - Suite 640
City/State/Zip: Wichita, Kansas 67202
Contact Person: Jerry Zorger
Phone: 316/264-2375

4620 feet from South line of Section
660 feet from East line of Section
IS SECTION X REGULAR YRREGULAR?

CONTRACTOR: License #: 5929
Name: DUKE DRILLING CO., INC.

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Ness
Lease Name: WOLFE Well #: 1

Well Drilled For: Well Class: Type Equipment:
X... Oil ... Enh Rec X. Infield X. Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... CWWD ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes ... Other
... Other

Is this a Prorated/Spaced Field? yes X no
Target Formation(s): Lansing, Mississippian
Nearest lease or unit boundary: 660'

If CWWD: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Ground Surface Elevation: 2244' feet MSL
Water well within one-quarter mile: yes X no
Public water supply well within one mile: yes X no

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:
Bottom Hole Location:

Depth to bottom of fresh water: 430'
Depth to bottom of usable water: 850'
Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 250'

Length of Conductor pipe required: N/A
Projected Total Depth: 1400'
Formation at Total Depth: Mississippian

Water Source for Drilling Operations:
... well ... farm pond X ... other

Will Cores Be Taken?: yes X no
If yes, proposed zone:

220' Alt. II Req.

Exp. 10/5/96

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

It is agreed that the following minimum requirements will be met:

APR 0 1996

05-06-1996

Pusher Rich Chapman
SPUD DATE 4-13-96 INIT. SP
LENGTH SURFACE PLANNED 250 SF
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 3 3/4" @ 24' CONDUCTOR
ANHYDRITE T- 1522 B- 1555 ELEVATION
TD 1570 FORMATION
KAR PIPE @ DV TOOL ALT II DONE
Arbuckle Plug @ 150' Ft. W/ 50 SX
Inj./Council @ Ft. W/ SX
Anhydrite Base @ 1550 Ft. W/ 850 SX
1/2 Base Anyh. @ 680' Ft. W/ 80 SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ 296 Ft. W/ 40 SX
40' Plug @ 46 Ft. W/ 10 SX
RAT HOLE CIR/W 15 SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well Pond Hauling
TECHNICIAN SL DATE 4-19-96
TYPE OF CEMENT 60/40 ft. 6' pipe 9 1/4" based
STARTING TIME (AM/PM) DATE
COMPLETION TIME (AM/PM) DATE 4/20
CEMENT COMPANY YLL Coal