

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23180-00-00
Spot: CSESESE Sec/Twnshp/Rge: 19-17S-21W
330 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: STIEBEN Well Number: 1
County: NESS Total Vertical Depth: 4375 feet

Operator License No.: 31627
Op Name: WHITETAIL CRUDE, INC
Address: N HWY 283 PO BOX 544
NESS, KS 67560

Conductor Pipe: Size feet: 8 1/4 2.19
Surface Casing: Size 8.625 feet: 255
Production: Size 5.5 feet: 4372 WITH 160 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/27/2001 3:15 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: ROGER Company: SWIFT SERVICES, INC. Phone: (785) 798-2300

Proposed Plugging Method: PUMP 200# HULLS & 30 SX CMT FOR BOTTOM PLUG. PUMP 18 SX GEL & 140 SX CMT. PUMP 5 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/27/2001 6:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 4350'. PERFS AT 4301-4304'. HAS BEEN 2 STAGED FROM 1700' TO SURFACE WITH 250 SX CMT. PUMP 200# HULLS & 30 SX CMT FOR BOTTOM PLUG. PUMP 18 SX GEL & 140 SX CMT. MAXIMUM PRESSURE 1600#. SHUT IN WITH 1200#. TIE ONTO BACKSIDE & PUMP 5 SX CMT. PRESSURED TO 600# AND HELD.

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: Q1

Signed

Michael Maier

(TECHNICIAN)

KANSAS CORPORATION COMMISSION

01-08-2002
JAN 08 2002

INVOICED DEC 28 2001

DATE Jan 9, 02

CONSERVATION DIVISION

WV NO. 2002061220

[Signature]
Form CP 2/3