

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-24214-00-00  
Spot: S2SESWSE Sec/Twnshp/Rge: 14-17S-21W  
110 feet from S Section Line, 1680 feet from E Section Line  
Lease/Unit Name: SHIRLEY Well Number: 1  
County: NESS Total Vertical Depth: 4215 feet

Operator License No.: 5663  
Op Name: HESS OIL COMPANY  
Address: PO BOX 1009  
MCPHERSON, KS 67460

Production Casing Size: 5.5 feet: 4215 WITH 350 SX CMT  
Surface Casing Size: 8.625 feet: 215 WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/12/2003 2:10 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: ARNIE HESS Company: HESS OIL COMPANY Phone: (620) 241-4640

Proposed Plugging Method: PUMP 500# HULLS & 25 SX CMT. GEL SPACER TO 1440'. CMT TO SURFACE 1440-0'. PUMP 50 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS IF NEEDED.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 08/12/2003 3:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PERFS AT 4137-52'. CIBP @ 4130'. PERFS AT 4078-83'. DV TOOL @ 1440'. CIRCULATED. PUMPED 35 SX CMT & 200# HULLS ON BOTTOM. PUMP 19 SX GEL & 115 SX CMT. PRESSURED TO 2000#. SHUT IN WITH 250#. TIED ONTO BACKSIDE & PUMPED 10 SX CMT. PRESSURED TO 500# AND HELD.

RECEIVED

AUG 25 2003


KCC WICHITA

08-25-2003

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Michael Maier  
(TECHNICIAN)

INVOICE #  
DATE 9-2-03  
NO. 2004-060467