

1060204

TO: STATE CORPORATION COMMISSION

API NUMBER 15-135-23,642 0000
W/2 SE SW SEC. 14, T 17 S, R 21 (W)

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3630 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME CONNOR WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY NESS 137.48

OPERATOR LICENSE # 4058 5/11

WELL TOTAL DEPTH 4230 FEET

OPERATOR: AMERICAN WARRIOR

PRODUCTION CSG: SIZE 4 1/2" @ 4226' WITH 575 SX

NAME AND PO BOX 399

SURFACE CASING: SIZE 8 5/8" @ 264' WITH 165 SX

ADDRESS GARDEN CITY, KS 67846

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR SWIFT SERVICES, INC LICENSE NUMBER 32382

ADDRESS PO BOX 466, NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 3:45 PM DAY: 11 MONTH: 05 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM ROGER

(COMPANY NAME) SWIFT SERVICES, INC (PHONE) 785-798-2300

WERE: PERFS AT 4112-4116

SET CIBP AT 4050' WITH 2 SX CEMENT. DV TOOL AT 1481' WITH 425 SX CEMENT THEN PERFORATED

AT 700' WITH 145 SX CEMENT. CEMENT CIRCULATED. GEL TO BASE OF THE ANHYDRITE THEN 80 SX

CEMENT TO TOP. PRESSURED TO 1000#. SHUT IN AT 1000#. WENT DOWN BACKSIDE PRESSURED RIGHT

UP TO 500# AND HELD.

_____ PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 4:30 PM DAY: 11 MONTH: 05 YEAR: 2000

ACTUAL PLUGGING REPORT _____

SET CIBP AT 4050' WITH 2 SX CEMENT. DV TOOL AT 1481' WITH 425 SX CEMENT THEN PERFORATED

AT 700' WITH 145 SX CEMENT. CEMENT CIRCULATED. GEL TO BASE OF THE ANHYDRITE THEN 80 SX

CEMENT TO TOP. PRESSURED TO 1000#. SHUT IN AT 1000#. WENT DOWN BACKSIDE PRESSURED RIGHT

UP TO 500# AND HELD.

REMARKS: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM)

I (DID) OBSERVE THIS PLUGGING. 5/22/00

Michael Maier SIGNED

(TECHNICIAN)

FORM C

STATE CORPORATION COMMISSION
Wichita, Kansas
MAY 19 2000
05-19-2000
CONSERVATION DIVISION

RECEIVED
STATE CORPORATION COMMISSION