

1060129

20,001-00-00

TO: STATE CORPORATION COMMISSION 10-21 API NUMBER 15-135-30-285
150'N OF SE NE SEC. 14, T 17 S, R 21 W

CONSERVATION DIVISION - PLUGGING SECTION 1830 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME ELMORE "D" WELL # 2

TECHNICIAN'S PLUGGING REPORT COUNTY NESS 134.81

OPERATOR LICENSE # 5663 WELL TOTAL DEPTH 4148 FEET

OPERATOR: HESS OIL COMPANY PRODUCTION CSG: SIZE 5 1/2" @ 4146' WITH 135 SX

NAME AND PO BOX 1009 SURFACE CASING: SIZE 8 5/8" @ 284' WITH 175 SX

ADDRESS MCPHERSON, KS 67460

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ALLIED CEMENTING LICENSE NUMBER N/A

ADDRESS PO BOX 628, GREAT BEND, KS 67530

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 21 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM

(COMPANY NAME) ALLIED CEMENTING (PHONE) 316-793-5861

WERE: 4094-96

1ST PLUG PUMPED 300# HULLS THEN 35 SX CEMENT TO BOTTOM.

2ND PLUG PERFORATED AT 850'. PUMPED 155 SX CEMENT. DIDN'T COME AROUND.

3RD PLUG TIED ONTO THE BACK SIDE PUMPED 25 SX CEMENT. SHUT OFF WITH 700# AND HELD.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 11:45 AM DAY: 21 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG PUMPED 300# HULLS THEN 35 SX CEMENT TO BOTTOM.

2ND PLUG PERFORATED AT 850'. PUMPED 155 SX CEMENT, DIDN'T COME AROUND.

3RD PLUG TIED ONTO BACK SIDE PUMPED 25 SX CEMENT. SHUT OFF WITH 700# AND HELD.

REMARKS: 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING. SIGNED Michael J. Maier (TECHNICIAN) FORM CP-2/3

10-30-1998



11-2-98
60239