

1060128

TO: STATE CORPORATION COMMISSION

10-21

API NUMBER 15-135-30,272-00-00
C NE NE SEC. 14, T 17 S, R 21 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME ELMORE "D" WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY NESS 133.12

OPERATOR LICENSE # 5663

WELL TOTAL DEPTH 4096 FEET

OPERATOR: HESS OIL COMPANY

PRODUCTION CSG: SIZE 4 1/2" @ 4094' WITH 135 SX

NAME AND PO BOX 1009

SURFACE CASING: SIZE 8 5/8" @ 402' WITH 200 SX

ADDRESS MCPHERSON, KS 67460

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ALLIED CEMENTING LICENSE NUMBER N/A

ADDRESS PO BOX 628, GREAT BEND, KS 67530

COMPANY TO PLUG AT: HOUR: 12:15 PM DAY: 21 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM

(COMPANY NAME) ALLIED CEMENTING (PHONE) 316-793-5861

WERE: OPEN HOLE

1ST PLUG CASING WAS SQUEEZED AT 885' WITH 200 SX CEMENT, 300# HULLS, & 25 SX CEMENT.

2ND PLUG MIX 13 BAGS GEL THEN 50 SX CEMENT. PRESSURED TO 1500# AND HELD. THEN MIXED

35 SX CEMENT DOWN BACK SIDE PRESSURED TO 600# AND HELD.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 1:15 PM DAY: 21 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG CASING WAS SQUEEZED AT 885' WITH 200 SX CEMENT, 300# HULLS, & 25 SX CEMENT.

2ND PLUG MIX 13 BAGS GEL THEN 50 SX CEMENT. PRESSURED TO 1500# AND HELD. THEN MIXED 35

SX DOWN BACK SIDE. PRESSURED TO 600# AND HELD.

REMARKS: 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Michael J. Maier (TECHNICIAN) FORM CP-2/3

11-2-98
60240

10-20-1998