

To: 1 070912
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-31
API NUMBER 15-135-22,171-00-00 11/12

SW'SW NW, SEC. 14, T 17 S, R 21 W/X
2970 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 30327
Operator: Peak Oil & Gas
Name & Address: RR 1, Box 6
McCracken, KS 67556

Lease Name Conners Well # 1
County Ness 136.66
Well Total Depth 4205 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 404

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:30 a.m. Day: 31 Month: 1 Year: 19 91

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4204' w/175 sx cement, PBDT 4143', Perfs at 4127-32'

1st plug sand back to 4080' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 10 sx gel and 50 sx cement at 1420',

3rd plug pump 10 sx gel and 50 sx cement at 700',

4th plug pump 125 sx cement at 440' to circulate.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 31 Month: 1 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4080' and dumped 5 sx cement on top of sand through bailer,

2nd plug pulled to 1409' and pumped down 5 1/2" 50 sx cement,

3rd plug pulled to 700' and pumped 50 sx cement,

4th plug pulled to 400' and circulated 45 sx cement to surface,

5th plug layed out casing and topped off with 20 sx cement.

FFR 8 1991
00-08-1991

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2300' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby acknowledge and observe this plugging.

DATE 2-22-91

INV. NO. 30815

Signed Dan Rankin (TECHNICIAN)

1-31 MAR 07 1991