

15-051-05 895-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-31

SW, Sec. 31, T 11 S, R 17 WE

330 feet from N SE section line

1650 feet from WE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5214

Lease Name Marshall A Well # 5

Operator: Fario Oil & Gas Co.  
Name & Address 301 South Market,  
Wichita, Ks. 67202

County Ellis

Well Total Depth 3500' feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 10 3/4" feet 1145'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 176, Chase, Ks. 67524

Company to plug at: Hour: 12:30 PM Day: 7 Month: 1 Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: Order 165 lbs 50 permit - 4 7/8 Gal. - 3 3/4 Gal. U., 5 lbs hully, 20 lbs Gel.

Signed John G. Lohle  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:00 PM Day: 7 Month: 1 Year: 1983

ACTUAL PLUGGING REPORT 10 3/4" - 1145' S.P. acc. w/ common, 7" set at 3621' w/ 135 lbs. 5 1/2" liner from 3400' to 3644'. Top perf at 3325'. Plugged bottom w/ 5 lbs cement, sand + 5 lbs cement to 3250'. L. hot pipe 2 times & recovered 1350'. Pumped in 10 3/4" S.P., 4 lbs hully, 15 lbs Gel., 65 lbs cement, 5 lbs Gel., 16 lbs hully, Released plug & followed w/ 100 lbs cement. Maximum pressure 660 pounds

Remarks: \_\_\_\_\_

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

Signed John G. Lohle  
(TECHNICIAN)

2-8-83  
2368-4

RECEIVED  
STATE CORPORATION COMMISSION

JAN 31 1983

CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
Rev. 9-82