

To: **6 062062**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-051-05994-0000
NE, SEC. 31, T. 11 S, R. 17 W/E
3300 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6509
Operator: Clar Mar Oil Co.
Name & Address: Box 1197
Hays, Kansas 67601

Lease Name C. M. Hadley Well # 3
County Ellis 118.76
Well Total Depth 3654 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1091

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rapid Well Services License Number 7049
Address Box 208 Russell, Ks. 67665

Company to plug at: Hour: 1:00 PM Day: 3 Month: Jan Year: 19 90

Plugging proposal received from Jim Clark

(company name) Clar Mar Oil Co. (phone) 913-625-3863

were: Order 200 sks 65/35 poz 8% gel.

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:00 PM Day: 4 Month: Jan Year: 19 90

ACTUAL PLUGGING REPORT 8 5/8" set at 1091' w/350 sks. 5 1/2" set at 3641' w/150 sks
Open hole at 13'. Ran wireline to 1120'. Perf two shots at 1100'. Pumped in 305 sks of
65/35 poz 8% gel followed w/5 sks gel in 5 sks cement and 5 sks gel w/8 sks hulls
mixed in last 15 sks cement and 10 sks gel, followed w/50 sks cement w/400 psi w/
good cement to surface.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: _____ JAN 17 1990

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 26 1990

INV. NO. 27183

Signed Gilbert G. Scheck
(TECHNICIAN)

Gilbert G. Scheck