

15-051-05417-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-153

NW, Sec. 31, T 11 S, R 17 WE

330 feet from NS section line

330 feet from WE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5214

Lease Name Marshall A Well # 17

Operator: Lario Oil & Gas Co.
Name &
Address 301 South Market,
Wichita, Ks. 67202

County Ellis

Well Total Depth 3649 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 1363'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 176, Chase, Ks. 67524

Company to plug at: Hour: 12:30 PM Day: 7 Month: 1 Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO Mellars Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: Order 165 lbs. 50% permix - 4% Gel. - 3% Cat. Oil, 5 lbs. bulls, 20
lbs. Gel, & 8 5/8" plug.

Signed Arthur J. Phil
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 6:00 PM Day: 7 Month: 1 Year: 19 83

ACTUAL PLUGGING REPORT 8 5/8" - 1363' SP, cnc. w/ common. 5 1/2" set at 3645' w/ 125
lbs. common. 3' of open hole. Lost plug & drilling line in hole.
Top perf at 3621'. Shot pipe 1 time & recovered 2833'.
Pumped in 8 5/8" SP, 5 lbs. bulls, 15 lbs. Gel, 65 lbs. cement, 5 lbs.
Gel, 1 lb. bulls, released plug & followed w/ 100 lbs cement.
Maximum pressure 650 pounds.

Remarks: _____

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / ~~did not~~) observe this plugging.

STATE CORPORATION COMMISSION

JAN 31 1983

Signed Arthur J. Phil
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 9-82

2-8-83
2367-W