

1 070713

8-25

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,288-~~4~~-00-01

E/2 E/2 SW, SEC. 20, T 17 S, R 21 W/R

1320 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4959

Lease Name Brenner Well # 1-20

Operator: ZPC Petroleum, Inc.

County Ness 141.02

Name & Address 9319 East Harry, Suite 122

Well Total Depth 4339 feet

Wichita, KS 67207

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 268

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor ZPC Petroleum, Inc. License Number 4959

Address 9319 East Harry, Suite 122, Wichita, KS 67207

Company to plug at: Hour: 10:30 a.m. Day: 25 Month: Year: 19 89

RECEIVED STATE CORPORATION COMMISSION
08-31-1989
AUG 31 1989
(phone) 913-625-7773

Plugging proposal received from Dean Ives

(company name) ZPC Petroleum, Inc.

were: 4 1/2" at 4339' CIBP at 4188' Perfs at 3908-3970'

1st plug pump 400 lbs. hulls and 30 sx cement, push plug,

perforate at 800',

2nd plug pump 100 sx cement in 4 1/2".

3rd plug pump 100 sx cement between 8 5/8" X 4 1/2" annulus.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:30 p.m. Day: 25 Month: 8 Year: 1989

ACTUAL PLUGGING REPORT 1st plug pumped 400 lbs. hulls and 30 sx Econolight cement,

rubber plug to 2500', perforated at 800'

2nd plug pumped 100 sx 60/40 Pozmix 6% gel down 4 1/2", circulated heavy drill mud,

Maximum pressure 600 psi.

3rd plug pumped 100 sx 60/40 Pozmix 6% gel down backside.

Maximum pressure 800 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel & Econolight by Halliburton. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 9-6-89

Signed Dan Gooden (TECHNICIAN)

WV. NO. 25809

8-25 NOV 06 1989