

To: 1 000083  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 135-23,237-~~100-03~~ <sup>K09</sup>  
W/2 SW SW, SEC. 20, T 17 S, R 21 W/8  
660 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT **9-23**

Operator License / 30083

Lease Name Brenner Well # 1 OWWO

Operator: G.A.B.S..Oil

County Ness 141.37

Name & Address  
1005 S. School  
Ness City, KS 67560

Well Total Depth 4350 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 268

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number

Address

Company to plug at: Hour: 2 p.m. Day: 23 Month: 9 Year: 19 96

Plugging proposal received from Brian Gabel

(company name) G.A.B.S. Oil (phone) 913-798-3115

Work: 4 1/2" at 4345' w/150 sx cement, PBSD 4315', Perfs at 4295-4301', DV @ 1400', circulated cement to surface  
1st plug fill casing with cement,

Check backside.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 3:30 p.m. Day: 23 Month: 9 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 225 sx cement.

Maximum pressure 1000 psi and shut in 400 psi.

2nd plug pumped down 8 5/8" X 4 1/2" annulus with 1 sx cement.

Maximum pressure 2000 psi and shut in 2000 psi.

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Richard M. Lucy (TECHNICIAN)

DATE 10-1-96

INV. NO. 46643

9-23

Rec  
9-30-96  
09-30-1996