

To: 051774
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-10

API NUMBER 15-135-23,397-00-00
NW NE SE, SEC. 27, T. 7 S, R. 21 W/X
2310 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5418
Operator: Allen Drilling Company
Name & Address: 6565 S. Dayton, Ste. 3800
Englewood, CO 80111

Lease Name McCormick Well # 1
County Ness
Well Total Depth 4285 139.26 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 310

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Halliburton License Number _____
Address Hays, KS

Company to plug at: Hour: 11:30 a.m. Day: 10 Month: 1 Year: 1994

Plugging proposal received from Jeff Zoller
(company name) Allen Drilling Company (phone) 303-799-6660

Perfs: 5 1/2" at 4283' w/475 sx cement, PBD 4248', DV @ 1443' w/350 sx cement, Perfs at 4120-29'
1st plug run tubing to 4130' and pump 20 sx cement and 100 lbs. hulls, pull to 3885' and pump
60 barrels gel,
2nd plug pull tubing to 1450' and circulate cement to surface,
3rd plug pull tubing and top off.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 5 p.m. Day: 10 Month: 1 Year: 1994

ACTUAL PLUGGING REPORT 1st plug ran tubing to 4130' and pumped 20 sx cement and 100 lbs.
hulls, pulled to 3885' and pumped 60 barrels gel,
2nd plug pulled tubing to 1450' and circulated cement to surface,
3rd plug pulled tubing and topped off with cement.

Red. 1-14-94
1-14-94
SH

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.
If additional description is necessary, use BACK of this form.)

INVOICES
I (did / ~~did not~~) observe this plugging.
DATE 1-19-94
WELL NO. 39732
1-10

Signed Richard W. Lacey
(TECHNICIAN)