

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15135-23,180-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Whitetail Crude, Inc KCC LICENSE # 31627
(owner/company name) (operator's)
ADDRESS P O Box 544 CITY Ness City, KS 67560-0544
STATE KS ZIP CODE 67560-0544 CONTACT PHONE # () 785-798-3641
LEASE Carl Stieben WELL# 1 SEC. 19 T. 17S R. 21W (~~East~~/West)
SE SE SE SPOT LOCATION/0000 COUNTY Ness

330 FEET (in exact footage) FROM S ~~XX~~ (circle one) LINE OF SECTION (NOT Lease Line)
330 FEET (in exact footage) FROM E ~~XX~~ (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS
SURFACE CASING SIZE 8 5/8 SET AT 255 CEMENTED WITH 160 SACKS
PRODUCTION CASING SIZE 5 1/2 SET AT 4372 CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4301-4304

ELEVATION 2215 T.D. 4375 P.B.T.D. 4350 ANHYDRITE DEPTH _____
(G.L./~~XXX~~) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Pump 30 sk plug of 60x46 & 200# of hulls to bottom. Pump gel spacer to 1700'. Finish filling 5 1/2 from 1700' up to surface w/cement. Pressure 5 1/2 to 500# & shut in. Check backside with 50 sk plug.
(if additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? no IS ACO-1 FILED? yes

If not explain why? no logs received at time of purchase

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Mike J. Fritzler, President Whitetail Crude, Inc PHONE# () 785-798-3641
ADDRESS P O Box 544 City/State Ness City, KS 67560-0544

PLUGGING CONTRACTOR Swift Services, Inc KCC LICENSE # 32382
(company name) (contractor's)
ADDRESS P O Box 466, Ness City, KS 67560-0466 PHONE # () 785-798-2300

PROPOSED DATE AND HOUR OF PLUGGING (if known?) ASAP 12-27-2001 @ 3:15 pm

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 12/26/01 AUTHORIZED OPERATOR/AGENT: Mike J. Fritzler
Mike J. Fritzler President

RECEIVED

DEC 31 2001
12-31-2001
WICHITA

10/02