

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**

(PLEASE TYPE FORM and File ONE Copy)

15-135-30292-0000

API # drilled 1966 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Hess Oil Company KCC LICENSE # 5663  
(owner/company name) (operator's)

ADDRESS P.O. Box 1009 CITY McPherson

STATE Kansas ZIP CODE 67460 CONTACT PHONE # (316) 241-4640

LEASE Elmore "D" WELL# 1 SEC. 14 T. 17 R. 21 ( /West)

- C - NE - NE SPOT LOCATION/QQQQ COUNTY Ness

660 FEET (in exact footage) FROM /N (circle one) LINE OF SECTION (NOT Lease Line)

660 FEET (in exact footage) FROM E/ (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET#

CONDUCTOR CASING SIZE  SET AT  CEMENTED WITH  SACKS

SURFACE CASING SIZE 8-5/8" SET AT 402' CEMENTED WITH 200 SACKS

PRODUCTION CASING SIZE 4-1/2" SET AT 4094' CEMENTED WITH 135 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: open hole 4094'-96'

ELEVATION /2182' T.D. 4096' PBD  ANHYDRITE DEPTH 1455'  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Per District office instructions

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? card IS ACO-1 FILED?

If not explain why?

**PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.**

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Bryan Hess/James C. Hess PHONE# (316) 241-4640

ADDRESS P. O. Box 1009 City/State McPherson, KS 67460

PLUGGING CONTRACTOR Hess Oil Company KCC LICENSE # 5663  
(company name) (contractor's)

ADDRESS P.O.Box 1009, McPherson, KS 67460 PHONE # (316) 241-4640

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Immediately

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 10-7-98 AUTHORIZED OPERATOR/AGENT: Bryan Hess  
(signature)

6/99

10-08-1998

6/99

15-125-20272-00-00

PICKRELL DRILG. CO.

#1 ELMORE 'D'

14-17-21  
C NE NE

Contr. CO TOOLS


NESS

County

E 2182 KBComm 10/29/66 Comp 12/8/66 IP ST TST: PMP 132 BOPD  
+ 1% WTR, GR 41

LOG Tops	Depth	Datum
*ANH	1455	+727
HEEB	3583	-1401
*TOR	3599	-1417
LANS	3622	-1440
B KC	3916	-1734
PAWNEE	3987	-1805
*FT SCOTT	4061	-1879
CHERO SHA	4074	-1892
1ST CHERO SD	4079	-1897
2ND CHERO SD	4086	-1904
3RD CHERO SD	4092	-1910
LTD	4096	-1914

Casing (CHERO 4094-96)  
8" 402/200 SX;  
4" 4094/100 SX;  
DST 4069-80/2 HRS, 85' MO, 45' SLI OC MW,  
BHP 925#/30", 416#/11', FP 62-72"  
DST 4080-89/PKR FAILED;  
DST 4085-89/45", 890' GIP, 185' CLN O, 125'  
MO, BHP 1039#/30", 1049#/45", FP 41-114"  
DST 4089-94/65", SB, 6/30", 950' CLN O, 1720'  
SLI MO, 80' OC MW, BHP 1049#/30", 1049#/  
11', FP 176-977"  
CO 4095; FU 200' O/11', FU 1600' O/14 HRS;  
BAILED MOY O/4 HRS; FU 100' O/4 HRS; CO 4096  
TD; SWB 20 BO 2000' OB; SWB 21' BOPH, GR 41  
UPSTART POOL OPENER



\* SMP TOP  
INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

15-125-20272-00-00  
 12



## Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Susan M. Seltsam, Commissioner Cynthia L. Claus, Commissioner

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

October 9, 1998

Hess Oil Company  
PO Box 1009  
McPherson, Ks. 67460

Elmore D #1  
API 15-13530272-00-00  
C NE NE  
Sec. 14-17S-21W  
Ness County

Dear Bryan Hess,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams  
Production Supervisor

District: #1  
304 W. McArtor  
Dodge City, KS 67801  
(316) 225-8888