

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

15-051-05566-0001

API NUMBER 6-23-43 (of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Cla-Mar Oil Company OPERATORS LICENSE NO. 6509 1/91

ADDRESS P.O. Box 1197, Hays, KS 67601 PHONE # (913) 625-3863

LEASE (FARM) C.M. Hadley "B" WELL NO. 4 WELL LOCATION CNL NE NE COUNTY Ellis

SEC. 31 TWP. 11 RGE. 17 (E) or (W) TOTAL DEPTH 3586' PLUG BACK TD 1280'

Check One:

OIL WELL _____ GAS WELL _____ D & A _____ SWD or INJ WELL X DOCKET NO. D-1582

SURFACE CASING SIZE 8 5/8" SET AT 1006' CEMENTED WITH 325 SACKS

CASING SIZE 5 1/2" SET AT 3523' CEMENTED WITH 250 SACKS

PERFORATED AT 784 - 910 4 1/2" Liner Set at 758' with 75 sacks
64 shots

CONDITION OF WELL: GOOD _____ POOR X CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL As outlined & Mr. Don Butcher
Mr. Bill Bryson at KCC.

Run tubing to 1215' open ended, place 200 sx common cement, then quickly set
tubing & packer at 750', pump in tubing with 65/35 poz 8% gel with cello flake
until pressure occurs. Clear tubing and packer with gel, release pressure,

(If additional space is needed use back of form) (over)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? ?
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 1-3-90 at 9:00 A.M.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Jim D. Clark PHONE # (913) 625-3863

ADDRESS P.O. Box 1197, Hays, KS 67601

PLUGGING CONTRACTOR Rapid Well Service LICENSE NO. 7049 JAN 3 1990

ADDRESS P.O. Box 208, Russell, KS 67665 PHONE # (913) 483-3362 CONSERVATION DIVISION
Wichita, Kansas

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Jim D. Clark
(Operator or Agent)

DATE: 1-2-90

(4)



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH MCCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

THIS NOTICE

APR 10 1990

EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

January 10, 1990
NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

Cla-Mar Oil Company
P.O. Box 1197
Hays, KS 67601

C.M. Hadley "B" 4
CNL NE NE
SEc. 31-11-17W
Ellis County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht
Shari Feist Albrecht
Director

District: #4 2301 E. 13th
Hays, KS 67601
(913) 628-1200