

15-135-20453-0000

SP

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 6 - 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Company and Southwest Petro-Chem.,  
Complete Address 705 Fourth National Bank Building Wichita, Kansas.  
Lease Name Dumler Unit Well No. 8  
Location App: -CSE-SE Sec. 2 Twp. 17 Rge. (E) (W) 26  
County Ness Total Depth 4500'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Pickrell Drilling Company,  
Address 705 Fourth National Bank Bldg., Wichita, Ks. License No.         
Operation Completed: Hour 2:30 PM Day 28 Month 6 Year 1971

The above well was plugged as follows:

236'--8 5/8" Surface casing, cement circulated with 140 Sx.  
Top of Dakota section @ 550'.  
        
Circulated hole with heavy mud. Pulled DP to 750' and displaced 100 Sx. cement thru  
DP from 750' to 425'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from 245'  
to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to botom of  
cellar.  
        
      

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 7-7-71

INV. NO. 3939-W