

15-135-20423-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 18 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Pickrell Drilling Company

Complete Address 705 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Dumler Unit Well No. 7

Location C NW SE Sec. 2 Twp. 17 Rge. (E) (W) 26

County Ness Total Depth 4490'

Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling Company

Address Box 1082 Great Bend, Kansas License No. 623

Operation Completed: Hour 5 P Day 16 Month 5 Year 1973

The above well was plugged as follows:

Total Depth 4490' 8 5/8 csg set at 241' cwc 150 sk.

5 1/2 csg set at 4482' cw 175 sk cmt.

5 1/2 csg PBTD 4400' with perf. (4385-4388)

Filled 5 1/2 csg W/sd (4350-4400) Dumped 5 sk cmt W/dump bailer. (4315-4350)

Cutoff and recovered 2925' of 5 1/2 csg.

Pumped down 8 5/8 csg with 25 sk gel & water W/500 lbs hulls -70 sk cmt -10 sk gel

& water -released 8 5/8 plug and pumped 50 sk cmt. by Allied Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Messing
Well Plugging Supervisor

INVOICED

DATE 5/18/73

INV. NO. 7372-W