

15-135-20063-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
SEP 25 1967
09-25-1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Chief Drilling Company Inc.

Complete Address: P. O. Box 797 Great Bend Kansas

Lease Name Elmore "C" Well No. 1

Location C S/2 NE Sec. 2 Twp. 17 Rge. 21 (E) (W) X

County Ness Total Depth 4130'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 10:30 P Day 21 Month 9 Year 1967

The Above well was plugged as follows:

RTD 4130' 8 5/8 csg set at 412' cwc

Gunned Pits, circulated heavy mud, set cementing plug at 600' and displaced 65 sc cem.

thru drill pipe. Heavy mud to 390' set cementing plug and displaced 25 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. J. Massey
Well Plugging Supervisor

DATE 9/26/67

INV. NO. 6387-W